BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of work: Estimate for the work of: Improvements to road, drain and footpath in main and cross roads of CQAL layout in ward no. 08 Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	**903.60**	Removing and refixing stone slabs of drains and pointing in CM (1:3)	cum	80.56	Rupees Eighty and Fifty Six Paise Only
2	**491.11**	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
3	**4.14**	KSRRB M200-15.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry. A. Rubble Stone masonry in lime mortar. MORTH	cum	217.30	Rupees Two Hundred Seventeen and Thirty Paise Only
4	**69.35**	KSRB 4-1.2 : Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation** including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5348.76	Rupees Five Thousand Three Hundred Forty Eight and Seventy Six Paise Only
5	**200.80**	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	993.22	Rupees Nine Hundred Ninety Three and Twenty Two Paise Only
6	**200.80**	KSRB 5-11 : Providing and constructing non load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.28, PWD SR 2016-17	Sqm	758.96	Rupees Seven Hundred Fifty Eight and Ninety Six Paise Only
7	**75.30**	KSRB 4.2.7 : Providing and laying in position **reinforced cement concrete of design mix M25** with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works **in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc.,** including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13 / Item No. 4.12, PWD SR 2016-17	cum	6749.02	Rupees Six Thousand Seven Hundred Forty Nine and Two Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

19/04

E.E. (BTP DIV)

19/04

No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
8	**115.27**	Providing laying palin / reinforced cement concrete for Box Drain walls of thicknes 10cm to 20 cm including cenmtering shuttering form work etc. complete as per approved drawiong and design MORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture Page No. 265 / Item No. 37.59.2, PWD SR 2016-17	cum	11032.48	Rupees Eleven Thousand Thirty Two and Forty Eight Paise Only
9	5.88	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **- TMT bars Fe 500 Page No. 17 / Item No. 4.46.20, PWD SR 2016-17**	Tonne	59413.00	Rupees Fifty Nine Thousand Four Hundred Thirteen Only
10	**451.80**	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. Page No. 25 / Item No. 5.31.2, PWD SR 2016-17	cum	825.74	Rupees Eight Hundred Twenty Five and Seventy Four Paise Only
11	**1911.00**	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 Page No. 24 / Item No. 5.22, PWD SR 2016-17	Rmt	37.10	Rupees Thirty Seven and Ten Paise Only
12	**1911.00**	Machine cutting	Rmt	60.00	Rupees Sixty Only
13	**1092**	Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete. Page No. 25 / Item No. 5.29, PWD SR 2016-17	No	385.84	Rupees Three Hundred Eighty Five and Eighty Four Paise Only
14	**200.80**	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 122 / Item No. 15.80, PWD SR 2016-17	Sqm	27.56	Rupees Twenty Seven and Fifty Six Paise Only
15	**200.80**	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 122 / Item No. 15.81, PWD SR 2016-17	Sqm	69.96	Rupees Sixty Nine and Ninety Six Paise Only
16	**288.00**	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1698.00	Rupees One Thousand Six Hundred Ninety Eight Only
17	**1.22**	KSRRB M300- Wrought iron and mild steel welded work KSRRB M300-18. Wrought iron and mild steel welded work (using angles, square bars, tees and channel grills, grating frames, gates and tree guards of any size and design etc. including cost of screens and welding rods or bolts and nuts complete fixed in position but without the cost of excavation and concrete for fixing which will be paid separately complete as per specifications. (25 kg per sq mtr) Page No. 15 / Item No. 19.97, PWD SR 2016-17	Qty	385.84	

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

19/04
E.E. (BTP. DIV)
19/04

.o.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
18	831.11	A) KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (Page No. 132 / Item No. 17.1) Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 10.00 Km etc complete as per specifications and directions of engineer in charge of the work Page No. 134 & 140 / Item No. 17.10, PWD SR 2016-17	cum	106.00	Rupees One Hundred Six Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

19/04

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'. 19/04

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010